

DISTRICT THREE

	Contract No.	Project No.	Total Contract Encumbrance	Location	Description	Contractor
1.	34025	603275	\$19,916,790.07	Worcester	<p>BRIDGE REHABILITATION, BR# W-44-082 ROUTE I-290 EB & WB OVER CSX R.R. AND VARIOUS CITY STREETS</p> <p>Work on this project involves the replacement of the bridge deck on I-290 through the raised section of highway in downtown Worcester. The work area will begin at the I-290/Grafton Street ramps and continue easterly to a point just east of the Shrewsbury Street ramp. This structure crosses over several city streets, the commuter rail (CSX Railroad) and several parking lots. Work during the 2004 construction season comprises the full removal and replacement of the Eastbound deck. Work during the 2005 construction season comprises the same scope but on the westbound deck. Traffic on I-290 through the work area is restricted to two lanes in each direction. This will be the case during the deck replacements, but all lanes will open during the winter months.</p>	SPS NEW ENGLAND INC
2.	31172	601946	\$1,314,921.03	Maynard & Stow	<p>BRIDGE REPLACEMENT, M-10-001=S-29-008, WHITE POND ROAD OVER ASSABET RIVER</p> <p>Work on this project consists of the complete removal and replacement of the White Pond Road bridge over the Assabet River. Work includes the complete removal and replacement of the bridge structure, stabilization of the river bank and construction of new approaches to the bridge.</p>	OMNI CONSTRUCTION CORP
3.	32140	601976	\$3,596,634.34	Auburn	RECONSTRUCTION OF RTE 12	J H LYNCH &

DISTRICT THREE

	Contract No.	Project No.	Total Contract Encumbrance	Location	Description	Contractor
					<p>(SOUTHBRIDGE ST) FROM DRURY SQ. TO CHURCH ST. INCLUDING WIDENING BR# A-17-012 OVER DUNN'S BROOK</p> <p>The work consists of roadway reconstruction, construction of new signals, and the installation of signs, pavement markings, and landscaping on Southbridge Street (Route 12), from Church Street to Auburn Street. Also included is the rehabilitation of the Southbridge Street bridge over the Auburn Pond Outlet.</p>	SONS INC
4.	32302	600573	\$5,318,928.44	Natick	<p>ROADWAY RECONSTRUCTION AND RELATED WORK ON ROUTE 135 (EAST & WEST CENTRAL STREET) & ROUTE 27 (NORTH & SOUTH MAIN STREET)</p> <p>The project begins on West Central Street at the Framingham town line and continues east on to East Central Street to the Wellesley town line. It also includes the section of South Main Street (Route 27) between East Central Street and Cottage Street, Clarendon Street and Hayes Street. More extensive improvements are proposed in the downtown area, on East Central Street between North Main Street and Union Street. In this area pavement rehabilitation will be supplemented by geometric and signalization improvements. This project also includes enhancements which consist of: installation of a bituminous concrete parking lot, granite curb, stamped cement concrete sidewalks, fencing and</p>	D&R GENERAL CONTRACTING

DISTRICT THREE

	Contract No.	Project No.	Total Contract Encumbrance	Location	Description	Contractor
					landscape plantings at the Henry Wilson Cobbler Shop and landscaping of the pedestrian path that runs parallel to West Central Street from the existing parking lot west of Cemetery Street to Middlesex Avenue, which includes fencing and plantings at both entrances to the path; sidewalk construction on Middlesex Avenue, on the south side of the roadway from the entrance to the existing pedestrian path, across Washington Street to the limits of the existing sidewalk on Middlesex Avenue.	
5.	34001	602947	\$7,126,232.03	Hudson & Marlboro	<p>CONSTRUCTION OF A SECTION OF THE ASSABET RAIL TRAIL (4 MILES)</p> <p>This project consists of the construction of a 12 foot wide paved bicycle trail along the alignment of an abandoned railroad in the towns of Hudson and Marlborough. This work also includes the installation of an bikeway underpass at the Route 85 connector in Hudson, rehabilitation of an existing trestle bridge over the Assabet River, new cement concrete sidewalks at roadway intersections, traffic signal improvements, drainage system improvements and all associated bikeway appurtenances.</p>	S&R CORPORATION
6.	34057	600906	\$47,204,958.17	Worcester	RT.146 PROJECT, RT.146 SEGMENT FROM WALL 12 NORTH TO RT.I-290/QUINSIGAMOND AVENUE (HURLEY SQUARE) INCL. 5 BRIDGES	J F WHITE CONTRACTING CO

DISTRICT THREE						
	Contract No.	Project No.	Total Contract Encumbrance	Location	Description	Contractor
					The project entails construction of 1 mile segment of Route 146 between Providence Street and Brosnihan Square and reconstruction of 2 miles of local streets. The work also includes four bridges, retaining walls, traffic signals, lighting and landscaping.	
7.	34471	603759	\$1,510,490.00	District Wide	<p>HIGHWAY LIGHTING UPGRADES AT VARIOUS LOCATIONS</p> <p>The intent of this project is the upgrading of highway lighting as assigned within the limits of District 3. The work to be done under this contract shall consist of furnishing all necessary materials, labor and equipment to upgrade and/or maintain in satisfactory operating condition.</p>	COVIELLO ELECTRIC & GENERAL
8.	34485	602459	\$3,083,207	Leominster	<p>BRIDGE REHABILITATION, BR# L-08-002 ROUTE 13 (MAIN STREET) OVER THE NORTH NASHUA RIVER</p> <p>The purpose of this project is to rehabilitate / strengthen the existing stone masonry arches and incorporate roadway and bridge safety improvements.</p>	FRANCHI EQUIPMENT CO INC
9.	34574	12650	\$6,276,139.69	Millville	<p>5 BRIDGE REPLACEMENTS ON CENTRAL STREET, BR# M-24-001, M-24-002, M-24-003, M-24-006 & M-24-007</p> <p>The Millville Contract 2 includes the reconstruction of 5 replacement bridges and approximately 1800 feet of roadway along Central Street and Main</p>	B & E CONSTRUCTION CORP

DISTRICT THREE

	Contract No.	Project No.	Total Contract Encumbrance	Location	Description	Contractor
					<p>Street in the Town of Millville. Two of the bridges span over branches of the Blackstone River. Two other bridges span old canals (or raceways) adjacent to the river. These four bridges are in deteriorated condition and will be entirely reconstructed as part of the project. The fifth bridge is a temporary panel bridge spanning over the P&W railroad. The temporary bridge was recently constructed as part of "Millville Contract 1". The intent of Contract 1 was to provide increased vertical clearance over the railroad in advance of reconstructing the other 4 bridges along Central Street. The project includes the necessary roadway reconstruction along Central Street, Lincoln Street and Main Street to accomplish the bridge work. Central Street will be widened by about 10 feet to the West to provide for an additional sidewalk and adequate roadway width for staged construction. Main Street will be shifted to the North by about 10 feet at the intersection with Central Street to provide improved intersection geometry. Properties at the Northeast and Northwest corners of Main and Lincoln Streets will be acquired by spot taking to provide the necessary right-of-way at the Intersection.</p>	
10.	34612	603413	\$427,088.03	Uxbridge	<p>BRIDGE REHABILITATION, BR# U-02-009, ROUTE 16 (MENDON STREET) OVER THE MUMFORD RIVER</p> <p>Work under this contract consists of replacing the</p>	AETNA BRIDGE CO

DISTRICT THREE						
	Contract No.	Project No.	Total Contract Encumbrance	Location	Description	Contractor
					bridge sidewalk and railing with a structural sidewalk, concrete rail with ornamental pedestrian handrails.	
11.	34633	602845	\$1,775,725.72	Wayland	<p>TRAFFIC SAFETY IMPROVEMENTS ON ROUTE 20 (BOSTON POST ROAD) @ ROUTE 27/126 (COCHITUATE ROAD)</p> <p>The work under this project includes reconstructing West Main Street (Route 20) from Beach Street to Granger Boulevard. Work includes widening and reconstruction, traffic signalization, drainage improvements, sidewalks, curbing, pavement markings, signing and landscape improvements.</p>	A R BELLI INC
12.	36127	603754	\$817,800.00	District Wide	<p>SCHEDULED AND EMERGENCY BRIDGE SHIELDING</p> <p>Contract will consist of installing bridge shielding by assignment throughout the District. Actual work and locations are defined by assignment</p>	J & J CONTRACTORS INC
13.	36494	600904	\$59,875,119.00	Worcester	<p>ROUTE 146 PROJECT, ROUTE I-290, QUINSIGAMOND AVENUE COMPLEX (BROSNIHAN SQUARE)</p> <p>The project entails the construction of the I-290/Route 146 (Brosnihan Square) interchange. The work includes the construction of 1 mile of Route 146, 1.3 miles of I-290 and 1.1 miles of local roads. The work also includes five bridges, retaining walls, traffic signals, lighting and extensive landscaping.</p>	J F WHITE CONTRACTING CO
14.	38363	NA	\$63.00	Middleton	Middleton, Layout No. 7871, Dated: 12/1/2004,	NA

DISTRICT THREE

	Contract No.	Project No.	Total Contract Encumbrance	Location	Description	Contractor
					Parcels 3-D-5 & 3-TE- Land Taking & Relocation	
15.	38915	604201	\$7,848,257.57	Gardner & Westminster	RESURFACING AND RELATED WORK, ROUTE 2 TO ROUTE 140N The purpose of this project is to resurface Route 2 from the Route 2 Bridge over Route 2A in Gardner easterly to the Route 2 Bridge over Route 140N in Westminster, a distance of approximately 3.5 miles.	P J KEATING CO
16.	39722	600981	\$4,118,879.00	Franklin	3R PROJECT UNION STREET FROM BEAVER ST TO WASHINGTON STREET (1.0 MILE) The reconstruction of Union Street also includes two concrete sidewalks with granite curbs, wheelchair ramps, geometric and drainage improvements, pavement markings and signs to improve vehicular and pedestrian safety.	Walsh Company, Inc., W.
17.	39932	602999	\$1,175,752.00	Bellingham	BRIDGE REPLACEMENT, BR# B-06-001, PEARL STREET OVER THE CHARLES RIVER The new bridge will be built beside the existing bridge. The existing bridge will remain open during construction. All work is being done behind existing retaining walls to minimize environmental impacts.	WALSH CONTRACTING CORP
18.	42382	604588	\$4,118,879.00	Lancaster & Leominster	INTERSTATE RESURFACING, ROUTE I-190	P J KEATING CO
19.	43257	604460	\$1,521,401.00	District Wide	Tree Trimming and Sight distance Clearing at Various Locations	Northern Tree Service Inc.

DISTRICT THREE

	Contract No.	Project No.	Total Contract Encumbrance	Location	Description	Contractor
20.	43792	604202	\$4,648,294.50	Westminster	<p>WESTMINSTER- RESURFACING AND RELATED WORK, ROUTE 2 OVER ROUTE 140N TO EXIT 26</p> <p>The westerly limit of Rte 2 in Westminster is Bridge W-28-021 over Route 140 North (mm 89.9±). The easterly limit of Rte 2 in Westminster is a pavement joint in the vicinity of Exit 26 (mm 92.4±). The total length of this project is approximately 2.5 miles.</p>	J H LYNCH & SONS INC
21.	43803	602930	\$2,502,082.00	Brookline & Westboro	<p>TRAFFIC SIGNS ON ROUTE 9</p> <p>This project will replace and update all overhead and ground-mounted guide sign panels, exit gore, warning, regulatory, and route marker panels on Route 9 and Brookline town line to I-495 in Westborough, with the exception of signing which was updated under the I-495 Milford to Bolton contract. secondary roadways from the Boston-Brookline town line to I-495 in Westborough, with the exception of signing which was updated under the I-495 Milford to Bolton contract.</p>	Liddell Brothers, Inc.
22.	43926	604505	\$703,120.00	District Wide	TRAFFIC SIGNAL BETTERMENT	Coviello & Sons, Inc., Chris
23.	44010	602135	\$6,074,788.00	Medway	<p>HIGHWAY RECONSTRUCTION, ROUTE 126 (SUMMER STREET) FROM BELLINGHAM T.L. TO HOLLISTON T.L</p> <p>The total length of this full depth reclamation, signal improvement project is approximately 2.65 miles, between Village Street and the Holliston Town</p>	PAOLINI CORP

DISTRICT THREE

	Contract No.	Project No.	Total Contract Encumbrance	Location	Description	Contractor
					Line. This project will result in the construction of two 12 foot travel lanes, with 4 foot paved useable shoulders. A 5 foot bituminous concrete handicap accessible sidewalk is proposed on the west side of Summer Street for the entire length of project. Sidewalk is proposed for several sections on the east side for an approximate total length of 7000 feet. New Signals are proposed for the intersection of Summer Street (Route 126) and Milford Street (Route 109).	
24.	44339	603628	\$4,835,402.00	Lunenburg	BRIDGE REPLACEMENT, BR# L-17-010, LEOMINSTER-SHIRLEY ROAD OVER THE B&M RR & MBTA This project is essentially the replacement of the Leominster-Shirley Road Bridge over the B&M RR. The new bridge will have a three span steel supported deck structure with new abutments behind the existing abutments. A temporary bridge will be used to manage traffic while the existing bridge is under construction. The work includes full depth reconstruction of the roadways approaching the bridge, drainage system improvements, granite curb installation, cement concrete sidewalks, hot mix asphalt driveway construction, pavement markings and sign installation, and other necessary landscaping.	P GIOIOSO & SONS INC
25.	44341	603451	\$5,733,934.52	Clinton	BRIDGE REPLACEMENT, C-16-003, ROUTE 62 & 70 (BOYLSTON STREET & CHESTNUT STREET) OVER THE NASHUA RIVER	S & R Corporation

DISTRICT THREE

	Contract No.	Project No.	Total Contract Encumbrance	Location	Description	Contractor
					<p>The work under this project consists of the replacement of the Boylston-Chestnut Street bridge (Route 62 & 70) over the Nashua River. The proposed structure will be a two-span bridge similar in width and span lengths to the existing bridge. A 42.5 foot wide bituminous concrete wearing surface and reinforced concrete deck will be supported by steel girders. A new center pier and abutments will be constructed. Stage construction will be used, maintaining one lane of traffic in each direction. The new bridge will be widened approximately 2.7 feet along the west side to facilitate two-lane traffic during construction. A new 6 foot handicap accessible sidewalk will be constructed on both sides of the bridge.</p>	
26.	44755	603481	\$6,217,804.00	Worcester	<p>HIGHWAY RECONSTRUCTION, GODDARD MEMORIAL DRIVE (FROM ROUTE 9 TO AIRPORT DRIVE)</p> <p>The project involves highway reclamation/reconstruction, widening, and median reconstruction from Apricot Street (near Route 9) to Airport Drive, a distance of approximately 2.30 miles.</p>	P J ALBERT INC
27.	44828	603336	\$5,845,665.00	Harvard & Shirley	BRIDGE REPLACEMENT, BR# H-09-025=S-13-018, HOSPITAL ROAD OVER THE NASHUA RIVER	SPS New England, Inc.
28.	45564	602522	\$5,390,503.50	Framingham	BRIDGE REPLACEMENT, BR# F-07-006, ROUTE 9 OVER THE SUDBURY RIVER	E. T. & L. Corp

DISTRICT THREE

	Contract No.	Project No.	Total Contract Encumbrance	Location	Description	Contractor
					This project proposes to replace the Route 9 Bridge over the Sudbury River and includes minor incidental roadway work.	
29.	48023	602944	\$1,597,322.00	Framingham	<p>BRIDGE REHABILITATION, BR# F-07-005, MAIN STREET OVER SUDBURY RIVER</p> <p>The proposed Main Street Bridge Rehabilitation Project includes repair of the existing bridge abutments along with replacement of deteriorated steel truss members. Minor approach work will include guardrail, pavement markings and minor repair to the historical bridge rail and elliptical trusses. The bridge will continue to be closed during the construction period and a detour will be in place.</p>	JAMES A GROSS INC
30.	48029	602952	\$8,936,169.08	Worcester	<p>WASHINGTON SQUARE IMPROVEMENTS</p> <p>This project consists of the replacement of the Washington Square Rotary with a two lane round-about.</p>	J H LYNCH & SONS INC
31.	49421	602138	\$944,920.00	Worcester	<p>BRIDGE REHABILITATION, BR# W-44-024, EXETER STREET OVER CSX RAILROAD</p> <p>The proposed project consists of replacing the existing bridge with a concrete deck beam bridge in the same location. The project will also involve the reconstruction of Exeter Street from 80 feet south of the bridge to 90 feet north of the bridge, cement concrete sidewalks, and installation of steel beam</p>	CONSTRUCTION DYNAMICS INC

DISTRICT THREE						
	Contract No.	Project No.	Total Contract Encumbrance	Location	Description	Contractor
					guardrail.	
32.	49495	604565	\$805,145.00	District Wide	FENCE REPAIR AT VARIOUS LOCATIONS ALONG INTERSTATE	Delucca Fence Co.
33.	51236	603331		Fitchburg & Leominster	<p>IMPROVEMENTS & SIGNALIZATION OF ROUTE 12 (PHASE I & II)</p> <p>Phase 1 improvements will include minor pavement widening along the Route 12 corridor to provide two 11.50-foot travel lanes and 8-foot shoulders. Intersection improvements at the junction of Route 12 and Bemis Road will include widening Route 12, realigning and widening Bemis Road, and the installation of new traffic signals. Phase 2 improvements will include minor pavement widening along the Route 12 corridor to provide two 11.50-foot travel lanes and 8-foot shoulders, adding auxiliary lanes on Route 12 at the Erdman Way intersection and upgrading the existing traffic signal at the intersection of Route 12 with Erdman Way. The proposed scope of work for both sections will also include new sidewalks and granite curbing on both sides of the roadway.</p>	Amorello & Sons, Inc. & Subs, A. F.
34.	51326	604413	\$3,769,040.00	District Wide	SCHEDULED AND EMERGENCY BRIDGE DECK AND JOINT REPAIRS (NORFOLK & SUFFOLK)	SPS New England, Inc.
35.	51392	603273	\$1,960,082.54	Hopedale	<p>BRIDGE REPLACEMENT, H-22-004, MILL STREET OVER THE MILL BROOK</p> <p>The proposed project consists of replacing the Mill Street Bridge over Mill Brook on the same</p>	JAMES A GROSS INC

DISTRICT THREE						
	Contract No.	Project No.	Total Contract Encumbrance	Location	Description	Contractor
					alignment with improvements to the approach roadway.	
36.	51421	604953	\$2,620,225.00	District Wide	MAINTENANCE OF STATE HIGHWAYS IN AREA B	BAY STATE CONST SERVICES INC
37.	51511	603190	\$4,533,769.00	Shrewsbury	<p>SIGNALIZATION & IMPROVEMENTS ON ROUTE 9 (TURNPIKE RD) FROM QUINSIGAMOND AVENUE TO MAPLE AVENUE (STREETSCAPE TRANSPORTATION ENHANCEMENT)</p> <p>This project is being undertaken as mitigation for the development of a Walgreens store at this location. The proposed work includes intersection realignment and minor widening along with the installation of new signal equipment, signs and pavement markings.</p>	J H LYNCH & SONS INC
38.	51611	603721	\$1,130,900.00	Princeton	<p>BRIDGE REPLACEMENT, P-16-014, ROUTE 62 (HUBBARDSTON ROAD) OVER WARE RIVER</p> <p>The work under this project consists of the replacement of the Route 62 (Hubbardston Road) Bridge over the Ware River (East Branch). The work will include complete replacement of the deck structure and construction of new abutments behind the existing abutments. The new bridge will be a single-span structure consisting of a concrete deck supported by precast concrete deck beams. The work will also include full-depth roadway reconstruction along the approaches to the bridge</p>	KODIAK CORP

DISTRICT THREE

	Contract No.	Project No.	Total Contract Encumbrance	Location	Description	Contractor
					for a total length of approximately 520 feet. A temporary bridge will be constructed adjacent to the existing bridge on the south side. The temporary bridge will provide one lane of traffic controlled by a traffic signal throughout the duration of construction.	
39.	51676	105121	\$5,356,086.00	Wayland	BRIDGE REPLACEMENT, W-11-001, ROUTE 20 OVER THE SUDBURY RIVER The subject bridge will be removed and replaced in its existing alignment. A temporary bridge will be in place during construction to maintain existing traffic patterns.	P GIOIOSO & SONS INC
40.	52244	604640	\$8,631,031.00	Milford & Southboro	INTERSTATE RESURFACING, ROUTE I-495 (SB ONLY)	P J KEATING CO
41.	52698	604536	\$1,576,190.00	District Wide	SCHEDULED AND EMERGENCY STRUCTURAL REPAIRS	SPS NEW ENGLAND INC
42.	52897	603505	\$725,772.00	Holden	BRIDGE REPLACEMENT, H-18-022, PRINCETON STREET OVER QUINAPOXET RESERVOIR MassHighway is proposing to rehabilitate the town-owned Princeton Street Bridge, which crosses over an outlet from the Quinapoxet Reservoir to the Quinapoxet River. The existing bridge's concrete abutments and corrugated iron arch will be repaired, and a protective coating will be applied to the exposed surface of the arch. A new concrete slab bridge deck will be constructed and will include a decorative bridge rail. New façade elements of the	Tasco Construction, Inc.

DISTRICT THREE						
	Contract No.	Project No.	Total Contract Encumbrance	Location	Description	Contractor
					bridge and rail will be faced with stone to match the existing stone facing of the bridge.	
43.	53146	601922	\$3,525,089.00	Shirley	<p>RESURFACING & BOX WIDENING ON TOWNSEND ROAD, FROM ROUTE 225 TO TOWNSEND T.L.</p> <p>The purpose of this project is to reconstruct Townsend Road from approximately ¼ mile south of the intersection of Groton Road to the Townsend Town Line. Also included is the reconstruction of Groton Road from approximately 625 feet east and 460 feet west of the Townsend Road. Other work includes drainage improvement, new highway guardrail, stone masonry retaining walls, pavement markings, traffic signs, and other incidental necessary works.</p>	Albert, Inc., P. J.
44.	53347	604714	\$1,015,350.00	District Wide	SCHEDULED AND EMERGENCY BRIDGE SUBSTRUCTURE REPAIR	N E L CORPORATION
45.	53508	602046	\$7,530,488.00	Framingham	<p>RECONSTRUCTION & SIGNALIZATION OF FRANKLIN STREET, INCLUDES F-07-030</p> <p>The proposed project consists of reconstructing Franklin Street from Howard Street to Main Street, in the Town of Framingham. The work will include geometric modifications, pavement rehabilitation, traffic signal installation and pedestrian safety improvements.</p>	PAVAO CONSTRUCTION CO INC
46.	53567	604140	\$3,011,145.00	Blackstone	BRIDGE BETTERMENT, SUPERSTRUCTURE RECONSTRUCTION, B-13-002, ROUTE 122 OVER THE BLACKSTONE CANAL & P&W RR	CONSTRUCTION DYNAMICS INC

DISTRICT THREE						
	Contract No.	Project No.	Total Contract Encumbrance	Location	Description	Contractor
					Replace bridge deck, beams, and railing.	
47.	53687	603359	\$1,607,493.00	Hopedale & Mendon	<p>SIGNAL & INTERSECTION IMPROVEMENTS @ ROUTE 140 & HARTFORD AVENUE</p> <p>The project will enhance safety and improve efficiency by installing a new traffic signal at the intersection of Route 140 and Hartford Avenue on the Hopedale-Mendon Town line. Hartford Avenue will be widened from its present 2 lanes to 4 lanes to reduce the existing delays at this intersection. This project will include the installation of crosswalks with wheelchair ramps and pushbutton pedestrian signals, as well as improved signs, drainage and pavement markings.</p>	P J KEATING CO
48.	53915	604719	\$1,167,100.00	District Wide	SCHEDULED & EMERGENCY BRIDGE DECK REPAIRS AT VARIOUS LOCATIONS	SPS New England, Inc.
49.	53925	604362	\$7,493,747.00	Littleton & Westford	<p>INTERSTATE RESURFACING ON I-495</p> <p>This project consists of resurfacing Interstate 1-495 from the Boxborough/Littleton town line, northerly to the bridge over Boston Road in Westford.</p>	P J KEATING CO
50.	53993	604901	\$1,181,740.40	District Wide	APPLICATION OF REFLECTORIZED PAVEMENT MARKINGS AT VARIOUS LOCATIONS	Traffic Markings, Inc.
51.	54045	603276	\$1,963,471.00	Sherborn	<p>BRIDGE REPLACEMENT, S-12-003, WHITNEY STREET OVER CSX R.R</p> <p>The proposed project consists of replacing the existing Whitney Street bridge over the CSX</p>	MIG Corporation, Inc.

DISTRICT THREE

	Contract No.	Project No.	Total Contract Encumbrance	Location	Description	Contractor
					railroad in its present location with minor improvements to the approach roadways. The bridge will be constructed in stages, keeping one lane of traffic open at all times.	
52.	54059	603537	\$1,502,200.70	Fitchburg	<p>RECONSTRUCTION OF NORTH STREET, FROM PEARL STREET TO ROSS STREET (PHASE III)</p> <p>The project involves resurfacing, minor box widening, sidewalk reconstruction, minor drainage improvements, street lighting, streetscape trees and the signalization of the Peal Street intersection. The project length is 0.31 miles.</p>	Barone Corp., P. V.
53.	54106	601975	\$9,121,759.00	Auburn	<p>RECONSTRUCTION OF ROUTE 12 (SOUTHBRIDGE STREET) FROM 200 FT. SOUTH OF CHURCH STREET TO ROUTE 20</p> <p>The proposed work consists of the reconstruction of Southbridge Street (Route 12) from the junction with Route 20 to just south of Church Street, for a distance of 2.9 kilometers (1.8 miles). The work will include roadway widening and pavement reconstruction, sidewalk reconstruction, horizontal and vertical alignment, drainage system improvements, traffic signal installation, landscaping, and safety improvements such as signing and pavement markings.</p>	LUDLOW CONSTRUCTION CO INC
54.	54311	603485	\$3,835,049.00	Rutland	RESURFACING ON ROUTE 68 (EAST COUNTY ROAD) FROM HOLDEN T.L. TO HUBBARDSTON T.L.	Massachusetts Broken Stone Company

DISTRICT THREE						
	Contract No.	Project No.	Total Contract Encumbrance	Location	Description	Contractor
					The project consists of roadway resurfacing/reclamation, and areas of full depth construction. The limits are from the Holden Town Line to the Hubbardston Town Line, a distance of approximately 5.75 miles.	
55.	54364	604611	\$2,117,227.12	Auburn, Oxford, & Webster	<p>TRAFFIC SIGN REPLACEMENT & IMPROVEMENTS ON I-395</p> <p>This project will replace and update all overhead and ground-mounted guide sign panels, exit gore, warning, regulatory, and route marker panels on the I-395 mainline and intersecting secondary roadways from the Connecticut/Massachusetts state border in Webster northerly to the U.S. 20 interchange in Auburn.</p>	HEIDI C SKEIRIK
56.	54380	604922	\$1,221,800.00	District Wide	DRAINAGE SYSTEM REPAIRS & IMPROVEMENTS AT VARIOUS LOCATIONS	Baystate Construction Services, Inc.
57.	54399	603480	\$2,079,097.00	Leicester	<p>RESURFACING & RELATED WORK ON ROUTE 56 (HUNTOON MEMORIAL HIGHWAY) FROM THE OXFORD T.L. TO PLEASANT STREET</p> <p>The project length is approximately 2 miles. The work will consist of roadway resurfacing/reclamation, and areas of full depth reconstruction to a section of Route 56 (Huntoon Memorial Highway), excluding the intersection of Stafford Street and Route 56 which is being</p>	J H LYNCH & SONS INC

DISTRICT THREE						
	Contract No.	Project No.	Total Contract Encumbrance	Location	Description	Contractor
					constructed as a separate safety improvement project.	
58.	54511	604984	\$648,376.75	District Wide	GUARDRAIL UPGRADES AND REPAIRS	DELUCCA FENCE COMPANY INC
59.	54537	604061	\$1,145,397.00	Gardner & Winchendon	<p>PEDESTRIAN & BIKE TRAIL CONSTRUCTION & RELATED WORK (NORTH CENTRAL PATHWAY - PHASE IV) INCLUDES W-39-016 & RESURFACING (GARDNER - PHASE III)</p> <p>This project consists of constructing a shared use path along a segment of the former Boston & Albany Railroad line from the vicinity of its intersection with Summer Street to the vicinity of its intersection with Glenallen Street, a distance of approximately 0.80 miles. The proposed path construction includes rehabilitation of one bridge, drainage system improvements, sidewalk construction, guardrail installation, roadside grading, pavement markings and signs, trailhead parking, landscaping and other incidental work. This is the fourth in a series of planned segments, which, when combined, will provide for a continuous North Central Pathway from Gardner to the New Hampshire border, a distance of approximately 16 miles.</p>	UEL Contractors, Inc.